



LOGGING ROAD OVER JOSIAS RIVER York, ME

CLIENT

Town of York
Public Works Department
186 York Street
York, ME 03909
(207)363-1011
Contact: Bill Bray (retired)

PROJECT COMPLETION

December 2006

DESCRIPTION

The Town of York suffered severe damage from the Mother's Day flood in 2006, which was a 100-year storm event. The Town contracted with CLD to design the replacement structure, to be funded through FEMA.

The new structure was a 20-foot-span precast arch founded on spread footings on bedrock buried under 15 feet of fill. CLD completed design, construction plans, and contract documents for advertising within 8 weeks of the storm to facilitate construction of the new structure, and opening of the roadway prior to the winter season.

CLD services included survey, preliminary and final design, coordination with the Town and FEMA representatives, as well as construction administration/observation.



- Emergency Replacement
- Bridge and Roadway Design
- Final Plans and Contract Documents
- Utility Coordination
- Construction Services