

LOWELL ROAD SIDEWALKS

Hudson, NH

CLIENT

Town of Hudson
Engineering Department
12 School Street
Hudson, NH 03051
(603) 886-6008
Contact: Gary Webster
Email: gwebster@hudsonnh.gov

LOCATION

Lowell Road
Hudson, NH

PROJECT COMPLETION

Construction Complete 2009

DESCRIPTION

CLD developed project plans for construction of approximately 2,100 linear feet of new sidewalks as part of a Transportation Enhancement project for the Town of Hudson on Lowell Road. This existing urban corridor was a mix of residential, commercial and industrial uses with extensive traffic and no pedestrian amenities.

Significant utilities existed within the corridor including overhead power, telephone and cable, as well as underground facilities for gas, telephone, sewer and water. The Town desired minimization of conflicts between proposed sidewalk and drainage facilities in order to eliminate utility relocation and streamline the construction schedule.



- Survey and Design
- Drainage
- Pedestrian Pathways
- Access Management / Traffic Calming
- Property Owner and Easement Acquisition Coordination
- Contract Documents
- Construction Oversight / Inspection
- Engineering Study

One of the key design goals was to improve access management and traffic calming through the reduction of open curb cuts across the frontages of businesses to improve the safety for pedestrians.

This project included new sidewalk construction, granite curbing, crosswalks, retaining walls, and associated drainage improvements along a main commercial street near the Town center. The new sidewalk provides a pedestrian pathway for neighborhoods adjacent to the Lowell Road corridor for connection to businesses, services, and schools.